MANY SIZES PA Insert terminators are available in 2", 4", 5", and 6" sizes. The 4" terminator is available in two models: a schedule 40 only, or in a special "step down" style which can be used with schedule 40 or schedule 20 pipe. All sizes can be supplied with form accessories making installation fast and easy.

EASY INSTALLATION Locators - similar to our tap-ons - attach terminators directly to the form or can be used to mount them on a knockout panel that can be reused numerous times. Pods - tall locators - allow the terminator to fit into a 6" wall without a knockout panel. Sizes 4", 5", and 6"come equipped with a flexible seal ring which conforms to the imperfections many older forms develop and keeps concrete slurry from leaking into the terminator cavity.

USEFUL TIPS

• Use a knockout panel with locators to mount terminators to the form. This allows for fewer holes in the form and reuse of the knockout panel.

• When knockouts cannot be used, try one of PA Inserts "pods", manufactured to make installation faster and more convenient.

### PVC Pipes used with PA Insert Terminators

Sizes	PVC I.D.	PVC 0.D.	TERM I.D.
2" Terminator SCH 40	2"	2.375"	2.387"
4" Terminator SCH 20 SCH 40	4" 4"	4.25" 4.5"	4.375" 4.5625"
5" Terminator SCH 40 SCH 80	5.017" 4.767"	5.563" 5.563"	5.5625" 5.5625"
6" Terminator SCH 40	6"	6.625"	6.625"

TO ORDER CALL 1-800-220-4857 or sales@pennsylvaniainsert.com

locators

1. Measure and mark the form where terminators are required, then bolt or nail locators or pods to the mounting panel or directly to the form.

2. The Terminators push on easily. Mount the panel or locators to the outside wall of the form. This puts the seal ring side of the Terminator (the side closer to the membrane) to the inside wall of the concrete structure.

3. When the form is closed the seal ring compresses against the wall and creates a smooth edge on the inside of the concrete structure that protects cables.