

Dome To Be Done By Others

Lifting Loop

1" Max

7'-0"

6" Sch 40 Steel Pipe  
Primed , Filled w/ Concrete

Decorative Polyethylene Sleeves Available

General Notes

- 1.) Concrete:  $f_c = 4,000$  PSI @ 28 Days Minimum
- 2.) Weight: 310 Lbs

Phoenix  
Precast  
Products

6" Pipe Filled  
Steel Bollard

P/N: SB-6PIPE