



- General Notes**
1. Concrete: $f_c = 5,000$ psi @ 28 Days Minimum, Type III Cement
 2. Steel Reinforcing Conforms to Latest ASTM Specifications
ASTM A-615 Grade 60 Rebar
 3. Design Loading: AASHTO-HS20-44
 4. Grates/Trash Racks Fastened with SS Hardware
 5. Grates/Trash Racks Finish Options: Galvanized, Painted, Or Unfinished

Phoenix Precast Products	Large Square Outlet Control Structure
---	--