



**General Notes**

- 1.) Concrete:  $f_c = 4,000$  PSI @ 28 Days Minimum
- 2.) Steel Reinforcement Conforms to Latest ASTM Specifications: ASTM A-615 Grade 60 Rebar
- 3.) Design Loading: AASHTO-HS20-44
- 4.) Closed End Boot on Inlet Side for 4" or 6" Pipe
- 5.) Pipe Bushing Required for Force Mains Into D-Box Less Than 4" Dia.
- 6.) Est Weights:

Box: 1,850 Lbs  
 Top Slab: 1,015 Lbs  
 Total: 2,865 Lbs

Phoenix  
 Precast  
 Products

3 Outlet HS-20  
 Velocity Reducing  
 "D" Box

P/N: