



Liquid Levels: 6' x 14' = 630 Gals/VF
 4" PVC = 2,992 Gals Inverts: Inlet-63"
 6" PVC = 2,942 Gals Inverts: Inlet-62"

General Notes:

1. Steel Reinforcement Conforms to Latest ASTM Specifications: ASTM-A615 Grade 60 Rebar
2. Concrete: $f_c = 5,000$ psi @ 28 Days Minimum
3. Flexible Sleeves Provided On All Pipe Connections
4. Butyl Rubber Joint Sealant Provided
5. Internal PVC Baffles Available Upon Request
6. Design Loading: AASHTO-HS20-44, ASTM C-890-06
7. Design Specified As: ASTM C-1227-08, ASTM C-913-08
8. Other Inlet/Outlet Pipe Sizes Available
9. Alarm, Float Levels, and all Ancillary Equipment Are Optional

Weights:
 Top Slab - 12,350 Lbs
 4' Riser - 12,450 Lbs
 Base - 12,500 Lbs
 Total Weight: 37,300 Lbs

Phoenix
 Precast
 Products

2,500 Gallon H-20
 Holding Tank

P/N: HT-2500H20