



Liquid Levels: 7' x 15' = 787 Gals/VF
 4" PVC = 4,525 Gals Inverts: Inlet-75"
 6" PVC = 4,462 Gals Inverts: Inlet-74"

- General Notes:**
1. Steel Reinforcement Conforms to Latest ASTM Specifications: ASTM-A615 Grade 60 Rebar
 2. Concrete: $f_c = 5,000$ psi @ 28 Days Minimum
 3. Flexible Sleeves Provided On All Pipe Connections
 4. Butyl Rubber Joint Sealant Provided
 5. Internal PVC Baffles Available Upon Request
 6. Design Loading: AASHTO-HS20-44, ASTM C-890-06
 7. Design Specified As: ASTM C-1227-08, ASTM C-913-08
 8. Other Inlet/Outlet Pipe Sizes Available
 9. Alarm, Level Floats, and All Ancillary Equipment Are Optional

Est. Weights:
 Top Slab - 15,450 Lbs
 5' Riser - 17,550 Lbs
 Base - 14,600 Lbs
 Total: 47,600 Lbs

Phoenix Precast Products	4,000 Gallon H-20 Holding Tank
	P/N: HT-4000H20