



Liquid Levels: 5' x 7' = 262 Gals/VF
 4" PVC = 1,113 Gals Inverts: Inlet-57"
 6" PVC = 1,092 Gals Inverts: Inlet-56"

Est. Weights:
 Top Slab - 4,750 Lbs
 Base - 13,200 Lbs
 Total: 17,950 Lbs

General Notes:

1. Steel Reinforcement Conforms to Latest ASTM Specifications: ASTM-A615 Grade 60 Rebar
2. Concrete: $f_c = 5,000$ psi @ 28 Days Minimum
3. Flexible Sleeves Provided On All Pipe Connections
4. Butyl Rubber Joint Sealant Provided
5. Internal PVC Baffles Upon Request
6. Design Loading: AASHTO-HS20-44, ASTM C-890-06
7. Design Specified As: ASTM C-1227-08, ASTM C-913-08
8. Other Inlet/Outlet Pipe Sizes Available
9. Alarm, Level Floats, and all Ancillary Equipment Are Optional

Phoenix
 Precast
 Products

1000 Gallon H-20
 Holding Tank

P/N: HT-1000H20

Concord, NH 03301