



**General Notes**

1. Steel Reinforcement Conforms to Latest ASTM Specifications: ASTM-A615 Grade 60 Rebar
2. Concrete:  $f_c = 4,000$  psi @ 28 Days Minimum
3. Design Loading: AASHTO- HS20-44
4. Distribution Line Running Across Chamber
5. Est Weight: 2,360 Lbs

Phoenix  
Precast  
Products

4Ft x 8Ft x 18In  
"S" Flow Diffuser  
Leaching Chamber