



**Liquid Levels: 6' x 14' = 630 Gals/VF**  
 4" PVC = 3,307 Gals Inverts: Inlet-69"  
 6" PVC = 3,257 Gals Inverts: Inlet-68"

**Weights:**  
 Top Slab - 12,350 Lbs  
 4' Riser - 12,450 Lbs  
 Base - 14,000 Lbs  
 Total Weight: 38,800 Lbs

General Notes:

1. Steel Reinforcement Conforms to Latest ASTM Specifications: ASTM-A615 Grade 60 Rebar
2. Concrete:  $f_c = 5,000$  psi @ 28 Days Minimum
3. Flexible Sleeves Provided On All Pipe Connections
4. Butyl Rubber Joint Sealant Provided
5. Internal PVC Baffles Available Upon Request
6. Design Loading: AASHTO-HS20-44, ASTM C-890-06
7. Design Specified As: ASTM C-1227-08, ASTM C-913-08
8. Other Inlet/Outlet Pipe Sizes Available
9. Alarm, Level Floats, and All Ancillary Equipment Are Optional

Phoenix  
 Precast  
 Products

3,000 Gallon H-20  
 Holding Tank

P/N: HT-3000H20

Concord, NH 03301