



General Notes

1. Concrete: $f_c = 4,000$ psi @ 28 Days Minimum
2. Supplied With or Without Locating Pins
3. Locating Pins = #4 Rebar x 18" Long
4. Est. Weight = 460 Lbs

Phoenix
Precast
Products

Truck Parking
Bumpers

P/N: PB-TRUCK