



Est Weight:

Vault - 12,900 Lbs
 Pad "A" - 2,225 Lbs
 Pad "B" - 1,925 Lbs
Total- 17,050 Lbs

General Notes

1. Reinforcement Steel Conforms to:
ASTM A615 Grade 60
2. Concrete: $f_c = 5,000$ psi @ 28 Days Minimum
3. Design Loading: AASHTO-H10
4. Built to GMP Spec K30.2

Phoenix
 Precast
 Products

Green Mountain Power
 K30.2 Assembly