



Est Weight:
 Vault - 16,750 Lbs
 Pad "A" - 4,150 Lbs
 Pad "B" - 2,325 Lbs
Total- 23,225 Lbs

General Notes

1. Reinforcement Steel Conforms to:
ASTM A615 Grade 60
2. Concrete: $f_c = 5,000$ psi @ 28 Days Minimum
3. Design Loading: AASHTO-H10
4. Built to GMP Spec K30.3

Phoenix
 Precast
 Products

Green Mountain Power
 K30.3 Assembly