



Est Weight:

Vault - 25,200 Lbs
 Pad "A" - 6,325 Lbs
 Pad "B" - 2,075 Lbs Each
Total- 35,675 Lbs

General Notes

1. Reinforcement Steel Conforms to:
ASTM A615 Grade 60
2. Concrete: $f_c = 5,000$ psi @ 28 Days Minimum
3. Design Loading: AASHTO-H10
4. Built to GMP Spec K30.5

Phoenix
 Precast
 Products

Green Mountain Power
 K30.5 Assembly