



Est. Weights:

Top Slab:	2,600 Lbs
Base:	4,450 Lbs
Total:	7,050 Lbs

General Notes

- 1.) Reinforcement Steel Conforms To ASTM A615 Grade 60
- 2.) Concrete: $f_c = 4,000$ psi @ 28 Days Minimum
- 3.) Meets or Exceeds PSNH Specifications

Phoenix
Precast
Products

PSNH
Grassy Area
Pull Box

P/N: PSNH-GAPB