



Est. Weights:	
Top Slab:	5,600 Lbs
Riser:	14,080 Lbs
Switchgear Cabinet:	6,750 Lbs
Base:	12,450 Lbs
Total:	32,130 Lbs

General Notes:

1. Steel Reinforcement Conforms to Latest ASTM Specifications: ASTM-A615 Grade 60 Rebar
2. Concrete: $f_c = 5,000$ psi @ 28 Days Minimum
3. Butyl Rubber Joint Sealant Provided
4. Design Loading: AASHTO-HS20-44, ASTM C-890-06
5. Design Specified As: ASTM C-1227-08, ASTM C-913-08
6. Exterior Coating Provided Except Switchgear Cabinet
7. Meets Or Exceeds PSNH Dwg # R-10001-2 Rev 1

**Phoenix
Precast
Products**

**PSNH R10001-2
Switchgear Cabinet
Assembly**

P/N: PSNHVAULT-2

Concord, NH 03301