



Lifting Loops
2 Places

Est Concrete: 0.08 c.y.

General Notes

- 1. Steel Reinforcement Conforms to Latest ASTM Specifications: ASTM-A615 Grade 60 Rebar
- 2. Concrete: $f_c = 4,000$ psi @ 28 Days Minimum
- 3. Liquid Capacity: 8.33 Gallons
- 4. Est Weight: 305 Lbs

Phoenix
Precast
Products

42" Diameter
Spill Pad