



General Notes

- 1. Steel Reinforcement Conforms to Latest ASTM Specifications: ASTM-A615 Grade 60 Rebar
- 2. Concrete: $f_c = 4,000$ psi @ 28 Days Minimum
- 3. Liquid Capacity: 79 Gallons
- 4. Est Weight: 1,600 Lbs

Phoenix
Precast
Products

72" Diameter
Spill Pad