



General Notes

- 1.) Concrete: $f_c = 4,000$ PSI @ 28 Days Minimum
- 2.) Weight: 465 Lbs

**Phoenix
Precast
Products**

**3-5-6-8-9 Outlet
"D" Box
Leveling Slab**

P/N: DBLS-3-5-6-8-9