



General Notes

1. Steel Reinforcement Conforms to Latest ASTM Specifications: ASTM-A615 Grade 60 Rebar
2. Concrete: $f_c = 4,000$ psi @ 28 Days Minimum
3. Design Loading: AASHTO- HS20-44
4. Distribution Line Running Across Chamber
5. Est Weight: 2,000 Lbs

Phoenix Precast Products	4Ft x 8Ft x 13In "S" Flow Diffuser Leaching Chamber
P/N: LC-4X8SHD	