



**General Notes**

- 1.) Reinforcement Steel Conforms To ASTM A615 Grade 60 #6 Rebar
- 2.) Concrete:  $f_c = 4,500$  psi @ 28 Days Minimum
- 3.) Meets or Exceeds PSNH Specifications
- 4.) Est. Weight: 12,600 Lbs

Phoenix  
Precast  
Products

PSNH 53-111  
3 Phase Transformer Pad  
75-500 KVA

P/N: PSNH-53111