



General Notes

- 1.) Reinforcement Steel Conforms To ASTM A615 Grade 60 #6 Rebar
- 2.) Concrete: $f_c = 4,500$ psi @ 28 Days Minimum
- 3.) Meets or Exceeds PSNH Specifications
- 4.) Est. Weight: 14,200 Lbs

Phoenix
Precast
Products

PSNH 53-116
3 Phase Transformer Pad
150-2,500 KVA

P/N: PSNH-53116