

Dome To Be Done By Others

Lifting Loop

1" Max

7'-0"

4" Sch 40 Primed Pipe Filled w/Concrete

Decorative Polyethylene Sleeves Available

General Notes

- 1.) Concrete:  $f_c = 4,000$  PSI @ 28 Days Minimum
- 2.) Est Weight: 170 Lbs

Phoenix Precast Products

4" Pipe Filled Steel Bollard

P/N: PB-4BP