



General Notes

- 1.) Concrete: Fiber, Fc = 4,000 PSI @ 28 Days
- 2.) Reinforcement: ASTM A-615, Grade 60
- 3.) Design Loading: AASHTO HS20-44
- 4.) Est. Weight: 800 Lbs

Phoenix
Precast
Products

Worcester Standard
Grade Ring

P/N: GRWSCB

Concord, NH 03301