



General Notes

1. Concrete: $f_c = 4,000$ psi @ 28 Days Minimum
2. Fiber Reinforcement
3. Steel Reinforcement: ASTM A615 Grade 60
4. Est Weight: 159 Lbs

Phoenix
Precast
Products

150 Lb
Mooring Weight

P/N: MW150

Concord, NH 03301