



General Notes

- 1. Concrete: $f_c = 4,000$ psi @ 28 Days Minimum
- 2. Fiber Reinforcement
- 3. 304 Stainless Steel Lifting Handle
- 4. Est Weight: 75 Lbs

Phoenix
Precast
Products

75 Lb
Mooring Weight

P/N: MW75