



## **Foundation And Backfill Notes:**

Tanks\Cistern\15K Cistern 3 Tanks (v)

**Phoenix Precast Products** 

- 1. Foundation Material Shall Be <sup>3</sup>/<sub>4</sub>" Crushed stone, Minimum 12" Thick, Compacted.
- 2. 1-½" Bank Run Gravel Shall Be Used For Backfill Operations Surrounding Tank. Backfill Shall Be Placed in Maximum 12" Loose Lifts. All Compaction Shall Be Done With Hand Operated Equipment.
- 3. Tank Excavation Shall Be Kept Dewatered Throughout Installation and Backfill Operations.
- 4. All Area Between Tanks Shall Be Filled To A Minimum Of 12" Above Crown Of Interconnection Pipe With ¾" Crushed Stone. 1-½" Bank Run Gravel May Be Used Above This Elevation.

	General Notes:
$\boxtimes$	1. Concrete: fc = 5,000 psi @ 28 Days Minimum Type III Cement
$\times$	2. Reinforcing Steel: ASTM-A615 Grade 60 Black Deformed Bars
$\times$	3. Design Loading: AASHTO-HS20-44, ASTM C-890-06
$\otimes$	Design Specified As: ASTM C-1227-08, ASTM C-913-08
$\times$	4. Butyl Rubber Joint Sealant Provided
$\times$	5. Includes Exterior Dampproofing
$\otimes$	6. Detail Drawings Provided Upon Request
$\times$	
$\times$	

Phoenix Precast Cistern Assembly (3 Tanks)

P/N: Custom As Required

Concord, NH 03301