



General Notes

- 1.) Concrete: $f_c = 4,000$ PSI @ 28 Days Minimum
- 2.) Weight: 1,300 Lbs

**Phoenix
Precast
Products**

National Grid
6" Diameter Bollard With
Base and Galvanized Pipe
Option #1

P/N: NG-6BGALV