



General Notes:

- Concrete: $f_c = 5,000$ psi @ 28 Days Minimum
- Reinforcing Steel: ASTM-A615 Grade #60. Min Cover = 1"
- Design Loading: AASHTO-HS20
- Item ID # Specified By Collar Type D or E
- Unistrut to be $1\frac{5}{8}$ " x $1\frac{5}{8}$ " x 6' Galvanized Steel Embedded in Wall & Tied to Reinforcement.

Phoenix
Precast
Products

Liberty Utilities
MS3467
Switchgear Manhole

P/N: LU-MS3467

Concord, NH 03301