



**General Notes**

1. Concrete:  $f_c = 4,000$  psi @ 28 Days Minimum
2. Steel Reinforcement: ASTM A-615 Grade 60 Black Deformed Bars
3. Size, Shape, and Location of Flow-Control Notch to Be Determined by Contractor Prior to Manufacture

Phoenix  
Precast  
Products

Outlet Control  
Weir Wall w/Base

P/N: Custom As Required

Concord, NH 03301