



Est Weights:	
Top Slab -	6,500 Lbs
Base -	20,500 Lbs
Total:	27,000 Lbs

General Notes

1. Concrete: $f_c = 5,000$ psi @ 28 Days Minimum Type III Cement
2. Steel Reinforcement Conforms to Latest ASTM Specifications: ASTM-A615 Grade 60 Black Deformed Bars
3. Design Loading: AASHTO-HS20-44 Design Specified as ACI 318-08, AASHTO-1992
4. Butyl Rubber Joint Sealant Provided
5. Flexible Sleeves Provided All Pipe Connections
6. Pipe Sizes and Compartment Configurations per Job Specifications

**Phoenix
Precast
Products**

**1,500 Gallon
3-Compartment HS-20
Oil & Sediment Separator**

P/N: Custom As Required

Concord, NH 03301