## General Notes

- 1. Concrete: fc = 5,000 psi @ 28 Days Minimum, Type III Cement
- 2. Steel Reinforcing Conforms to Latest ASTM Specifications ASTM A-615 Grade 60 Rebar
- 3. Design Loading: AASHTO-HS20-44
- 4. Grates/Trash Racks Fastened with SS Hardware
- Grates/Trash Racks Finish Options: Galvanized, Painted, Or Unfinished

Phoenix	Custom Outlet Control
Precast	Structure With
Products	Extended Base
P/N: Custom As Required	

Outlet Pipe Connection

Phoenix Precast Products

Concord, NH 03301