



General Notes

1. Concrete: $f_c = 5,000$ psi @ 28 Days Minimum Type III Cement
2. Steel Reinforcement Conforms to Latest ASTM Specifications: ASTM-A615 Grade 60 Black Deformed Bars
3. Design Loading: AASHTO-HS20-44 Design Specified as ACI 318-08, AASHTO-1992
4. Butyl Rubber Joint Sealant Provided
5. Pipe Sizes and Compartment Configurations per Job Specifications

**Phoenix
Precast
Products**

**Generic 3-Compartment
HS-20 Oil &
Sediment Separator**

P/N: Custom As Required

Concord, NH 03301