



Est Weight: 4,800 Lbs

P/N: Casting Only      BH-BC  
 P/N: Door Installed      BH-BDI  
 P/N: Door Not Installed      BH-BDD

**Not To Scale**

General Notes

- 1.) Concrete 4,000 psi Minimum After 28 Days
- 2.) Heavy Double Leaf Steel Doors Primed Not Painted

Phoenix  
Precast  
Products

Basement Entrance  
Type "B"

P/N: See Above

Concord, NH 03301