



Not To Scale

General Notes

- 1.) Concrete 4,000 psi Minimum After 28 Days
- 2.) Heavy Double Leaf Steel Doors Primed Not Painted

Est Weight: 5,500 Lbs

P/N: Casting Only BH-CC

P/N: Door installed BH-CDI

P/N: Door Not Installed BH-CDD

Phoenix
Precast
Products

Basement Entrance
Type "C"

P/N: See Above

Concord, NH 03301