



Est Weight: 2,400 Lbs

P/N: Casting Only BH-SC
 P/N: Door Installed BH-SDI
 P/N: Door Not Installed BH-SDD

Not To Scale

General Notes

- 1.) Concrete 4,000 psi Minimum After 28 Days
- 2.) Heavy Double Leaf Steel Doors Primed Not Painted

Phoenix
 Precast
 Products

Basement Entrance
 Type "S"

P/N: See Above

Concord, NH 03301