

Dome To Be
Done By Others

Lifting Loop

1"
Max

7'-0"

4" Sch 40
Primed Pipe
Filled w/Concrete

Decorative Polyethylene
Sleeves Available

General Notes

- 1.) Concrete: $f_c = 4,000$ PSI @ 28 Days Minimum
- 2.) Est Weight: 166 Lbs

Phoenix Precast Products	4" Pipe Filled Steel Bollard
P/N: PB-4BP	